

Braindump2go Guarantee All Exams 100% Pass One Time!

> Vendor: Cisco

## **Exam Code: 300-615**

# > Exam Name: Troubleshooting Cisco Data Center Infrastructure (DCIT)

# > New Updated Questions from <u>Braindump2go</u> (Updated in <u>Sep/2020</u>)

# Visit Braindump2go and Download Full Version 300-615 Exam Dumps

## **QUESTION 26**

Refer to the exhibit. The OSPF neighbor is stuck in the INIT state. Which cause of this issue is true?

NEXUS-1# show ip ospf neighbor Neighbor ID Pri State Dead Time Address Interface 10.1.5.1 1 INIT/- 00:00:34 10.10.1.1 ethernet 1/1NEXUS-1# NEXUS-2# show ip ospf neighbor Neighbor ID Pri State Dead Time Address Interface 10.1.5.1 1 INIT/-00:00:34 10.1.5.1 ethernet 1/1 NEXUS-2#

- A. An ACL is blocking unicast packets
- B. An ACL is blocking the hello packets.
- C. The ID of the router is the same as the ID of the neighbor.
- D. The MTU is misconfigured.

## Answer: B

Explanation:

https://www.cisco.com/c/en/us/support/docs/switches/nexus-7000-series-switches/116422-technote-ospf-00.html#anc6

## **QUESTION 27**

Refer to the exhibit. You are troubleshooting a Cisco FabricPath anycast HSRP configuration issue. What is the cause of the issue?

- A. L1 and L2 would not be connected.
- B. The switch ID that is used in each switch configuration must be different.
- C. The priority for S1 and S2 is the same in each switch configuration.
- D. HSRP version 2 must be used with HSRP any cast.

## Answer: D

Explanation:

An anycast HSRP bundle is supported only in HSRP version 2.

https://www.cisco.com/c/en/us/td/docs/switches/datacenter/sw/6\_x/nx-os/fabricpath/configuration/guide/b-Cisco-Nexus-7000-Series-NX-OS-FP-Configuration-Guide-6x/b-Cisco-Nexus-7000-Series-NX-OS-FP-Configuration-Guide-6x\_chapter\_0100.html#reference\_6B13C60D92374EF7B34B3F1FB779CD2E

## **QUESTION 28**

300-615 Exam Dumps 300-615 Exam Questions 300-615 PDF Dumps 300-615 VCE Dumps

https://www.braindump2go.com/300-615.html



**One Time!** 

Refer to the exhibit. Which result of the REST API configuration on a Cisco APIC is true?

<pre>\$APIC Address/api/policymgr/mo/.xml</pre>
<poluni></poluni>
<fabricinst></fabricinst>
<fabricooservicepol></fabricooservicepol>
<fabricrsoospath< td=""></fabricrsoospath<>
tDn="topology/pod-1/paths-\$LEAF Id/pathep-[eth1/49]"
<pre>lc="blacklist" status ="deleted" /&gt;</pre>
<pre>\$LEAF Address/api/node/mo/topology/pod-1/node-</pre>
\$LEAF Id/sys/action.xml
<actionlsubj odn="sys/phys-[eth1/49]"></actionlsubj>
<li><li>thifSetInServiceLTask adminSt='start'/&gt;</li></li>

- A. It recovers a disconnected leaf
- B. It deletes a leaf switch from eth1/49
- C. It recovers a disconnected APIC node
- D. It recovers a disconnected Spine


## Answer: A

### Explanation:

Recovering a Disconnected Leaf Using the REST API https://www.cisco.com/c/en/us/td/docs/switches/datacenter/aci/apic/sw/2x/rest\_cfg/2\_1\_x/b\_Cisco\_APIC\_REST\_API\_Configuration\_Guide/b\_Cisco\_APIC\_REST\_API\_Configuration\_Guide\_ch apter 01001.html?bookSearch=true#task E7CDCEE65C7441D78017E

## **QUESTION 29**

Refer to the exhibit. An engineer is configuring boot from iSCSI on a Cisco UCS B-Series Blade Server, but the LUN fails to mount. Which action resolves the issue?



- A. Statically configure the target information in the Boot Policy.
- B. Configure an MTU size of 9000 on the appliance port.
- C. Configure a QoS policy on the vNIC.
- D. Set a connection timeout value of 250 in the iSCSI Adapter Policy.

## Answer: A

## **QUESTION 30**

Refer to the exhibit. A web browser displays a "not secure" warning message when accessing the web interface of Cisco UCS Manager. Which action resolves the issue?


300-615 Exam Dumps 300-615 Exam Questions 300-615 PDF Dumps 300-615 VCE Dumps

https://www.braindump2go.com/300-615.html



# Braindump2go Guarantee All Exams 100% Pass

**One Time!** 



- A. Load third-party certificate to UCS Manager.
- B. Use the correct TCP port for HTTPS.
- C. Use a supported web browser.
- D. Use a supported version of UCS Manager.

#### Answer: A

#### **QUESTION 31**

An attempt to use a global vNIC redundancy template pair results in a service profile that fails to apply. Which action resolves the issues?

- A. Create the peer names before creating the templates.
- B. Assign the secondary template first, and then set the peer name.
- C. Assign both templates simultaneously.
- D. Assign the primary template first, and then set the peer name.

#### Answer: D

#### **QUESTION 32**

An engineer attempts to register Cisco UCS Manager to Cisco UCS Central, but the registration fails. The engineer can ping Cisco UCS Central from UCS Manager. Which two actions must the engineer attempt to resolve the problem? (Choose two.)

- A. Synchronize the date and time to NTP for Cisco UCS Central and the Cisco UCS domains.
- B. Apply the UCS Central license to UCS Central.
- C. Place Cisco UCS Manager on the same subnet as Cisco UCS Central.
- D. Allow port 443 between Cisco UCS Manager and Cisco UCS Central.
- E. Allow port 9443 between Cisco UCS Manager and Cisco UCS Central.

### Answer: AD

#### **QUESTION 33**

You have an ACI environment with three APICs, two spine switches, and four-leaf switches. You wipe and reboot all APICs first then leaf and spine switches one- by-one and successfully go through the Initial Setuo dialogue on the APIC

## 300-615 Exam Dumps 300-615 Exam Questions 300-615 PDF Dumps 300-615 VCE Dumps

https://www.braindump2go.com/300-615.html



## **One Time!**

1 CIMC KVM console. When you log in to the APIC1 WebGUI, you notice that you do not see any directly connected leaf switches being discovered under Fabric > Inventory > Fabric Membership. What is the cause of the issue?

- A. The leaf nodes were not erased properly, which caused a fabric parameters mismatch with the APIC1.
- B. Rebooting the APICs and the leaf and spine switches after wiping them is not required.
- C. You forgot to enter the TEP Pool value during the Initial Setup dialogue on APIC1.
- D. The same Fabric Name value should be used before after wiping all devices.

#### Answer: C

#### **QUESTION 34**

An engineer must replace a failed memory on a Cisco UCS B-Series Blade Server. After the replacement was done, the server has a "resolve slot" warning. Which server maintenance action resolves the issue?

- A. Perform diagnostic interrupt on the server.
- B. Re-acknowlegement the server.
- C. Reset the server.
- D. Decomission the server.

#### Answer: B

#### **QUESTION 35**

Cisco Unified Computing System Manager raises a critical error message that indicates that the system has overlapping Ethernet and FCoE VLANs. All of the Ethernet traffic on the overlapping VLANs drops. Which action resolves the issue?

- A. Modify the VLAN assignment to vNICs.
- B. Change the PIN groups on the vHBAs.
- C. Modify the FCoE VLAN.
- D. Set the FCoE VLAN as the native VLAN on server uplinks.

#### Answer: A

#### **QUESTION 36**

Refer to the exhibit. An engineer is performing a health check on ACI. Which statement about interface Ethernet 1/11 is true?



leaf1# show interface ethernet 1/11 Ethernet1/11 is up (out-of-service) admin state is up, Dedicated Interface Hardware: 1000/10000 Ethernet, address: e4aa/5d94.a2b5 (bia e4aa.5d94.a2b5) MTU 9000 bytes, BW 10000000 Kbit, DLY 1 usec reliability 255/255, txload 1/255, rxload 1/255 Encapsulation ARPA, medium is broadcast Port mode is trunk full-duplex, 10 Gb/s, media type is 10G FEC (forward-error-correction) : disable-fec Beacon is turned off Auto-Negotiation is turned on Input flow-control is off, output flow-control is off Auto-mdix is turned off Rate mode is dedicated Switchport monitor is off EtherType is 0x8100 EEE (efficient-ethernet) : n/a Last link flapped 4d06h Last clearing of "show interface" counters never 1 interface resets 30 seconds input rate 0 bits/sec, 0 packets/sec 30 seconds output rate 0 bits/sec, 0 packets/sec

- A. The interface is working correctly and fully operational, but it is not in use.
- B. The interface policy is misconfigured.
- C. "out-of-service" is the default interface status in ACI.
- D. "out-of-service" indicates that no service graph is in use for this interface.

## Answer: B

#### **QUESTION 37**

A user reports that they cannot reach from a UCS server to an FC Storage array. Which command is used to test communication between an FCF and a target?

- A. fcroute
- B. traceroute
- C. fcping
- D. ping

Answer: C